

Tess Electric Inc.

12142 Severn Way, Riverside CA 92803
Phone (951) 427-1735
Lic. 1057586

Quote Number# 0000452

April 11, 2024

To: Apple Valley Foothill
Attn: Daniel Smith

Project: Facilities Well Pump Starter & Site Upgrades

Tess Electric is pleased to provide the following proposal for the following scope of services and materials to be installed at the facilities Well 1 & 2 site:

Well 1 Pumphouse scope:

- Demo all existing electrical inside Well 1 pump house including: pump starter, existing empty pump starter panels, wire gutter, load panel, 480/ 120 transformer, existing 120v convenience receptacles, remove existing weathered conductors & motor leads.
- Existing SCADA cab. Shall be protected in place
- Provide and install [1] 40HP 600V 100A rated WEG GPH2050 motor starter & motor start enclosure
- Provide and install 50A transformer safety disconnect
- Provide and install new 480/120V 5KVA transformer
- Provide and install new 120/240v 4 space load panel
- Run all new conduit to electrical equipment, SCADA cab. Lighting and add [4] new receptacles
- Run new cable to from transfer switch to motor starter & to motor
- Provide and install new outside lighting [2] wall pack fixtures

Gen. Container Scope:

- Provide and install [2] 4ft LED light fixtures at far end (dark side) of container
- Provide and install all necessary conduit and wire for lighting and switches
- Provide [2] new outside wall pack lighting

Well 2 Pumphouse scope:

- Provide and install new outside lighting [2] wall pack fixtures

Sales tax is additional if applicable. Prices are good for 30 days, subject to change without notice. Please note that this is not an offer to contract, but merely a quotation of current prices for your convenience and information. Orders based on this quotation are subject to our acceptance on the terms and conditions stated in our written acknowledgement of order. We make no representations with respect to compliance with job specifications.

Tess Electric Inc.

12142 Severn Way, Riverside CA 92803

Phone (951) 427-1735

Lic. 1057586

Notes:

- All new light fixtures shall match
- Shipping Prepaid & Add
- Any minor pump nuisance failures shall be addressed

Materials.....	\$6,436.56
Tax.....	\$563.20
Labor.....	\$12,860.48
Total Cost.....	\$19,860.23

All material is guaranteed to be as specified. All work to be completed in a substantial workmanlike manner according to specifications submitted, per standard practices. Any alteration or deviation from the above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, and other necessary insurance. Our workers are fully covered by Workmen's Comp.

Sales tax is additional if applicable. Prices are good for 30 days, subject to change without notice. Please note that this is not an offer to contract, but merely a quotation of current prices for your convenience and information. Orders based on this quotation are subject to our acceptance on the terms and conditions stated in our written acknowledgement of order. We make no representations with respect to compliance with job specifications.